



**WEST BENGAL STATE FOOD PROCESSING
&
HORTICULTURE DEVELOPMENT CORPORATION LIMITED
(A GOVT. OF WEST BENGAL ENTERPRISE)
BENFISH TOWER (6th Floor)
31 - GN Block, Sector – V
KOLKATA – 700091**

NIQ No. 15/WBSFPHDCL/1770/2025-26


Date: 05-06-2025

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited from the eligible Contractors / Agencies having experience in similar type of work of “**New Construction of Vermicompost Unit at Farm – 2 at Ayeshpur Farm, Nadia**”. The intending agencies should quote the rate of “**New Construction of Vermicompost Unit at Farm – 2 at Ayeshpur Farm, Nadia**” at the space provided in Annexure – II. Details of the work is specified in Annexure – I.

TERMS & CONDITION

1. The bidder must submit the copy of Trade License (valid on the last date of submission of the Tender) and PAN along with the submission of bid.
2. The rate will be valid for 6(six) months from acceptance of the work order.
3. Rates should be quoted for “**New Construction of Vermicompost Unit at Farm – 2 at Ayeshpur Farm, Nadia**” at the mentioned place following the details of work including of all materials, labours, transportation and all taxes in Annexure-II in figure as well as in words.
4. **The Contractors / Agencies may quote their rates against the mentioned work in Annexure – II and drop the same in a sealed envelope during office hours in the tender box kept at the General Section of WBSFPHDCL office at the above mentioned address or at The Ayeshpur Farm Office of WBSFPHDCL starting from 05.06.2025 at 12:00 Noon (Date of Publication of NIQ) upto 13.06.2025 by 3:00 PM. Received quotations will be opened on same day at 4:00 PM.**
5. The Work Order is normally be issued to the L-1 Bidder for execution of the work. However, the Quotation Inviting Authority reserves the right to accepting a bid other than the lowest on a specific ground to be recorded in writing.
6. The successful Bidder has to complete the entire work within 15 (fifteen) days from the date of issue of work order.
7. Details may be seen in the office Website: www.ipshabengal.com
8. The Corporation reserves the right to accept or reject any or all bids and to annul the tendering process prior to issue of work order, without thereby, incurring any liability to the affected Bidder or Bidders or any liability to inform the Bidder of the ground for such action.
9. **Payment of Bill:**
 - i. Measurement of the work will be taken by the Authority within 5 (five) days from the date of completion of work.
 - ii. Bill will be released to the Contractor within 30 (thirty) days from the date of submission of Bill in duplicate with the certification of the concerned Engineer and copy of duly signed measurement sheet.



**Managing Director
W.B.S.F.P. & H.D.C.L.**

NIQ No. 15/WBSFPHDCL/1770/2025-26

Date: 05-06-2025

Copy to:

1. The B.D.O. Office, Haringhata with a request to display the Notice in the Office Notice Board.
2. The Prodhan, Birohi - I G.P. with a request to display the Notice in the Office Notice Board.
3. The Prodhan, Birohi - II G.P. with a request to display the Notice in the Office Notice Board.
4. The Farm In-Charge with a request to display the Notice in the Office Notice Board.
5. Notice Board of the office


Managing Director
W.B.S.F.P. & H.D.C.L.

Details of Work

Shondy

WEST BENGAL STATE FOOD PROCESSING & HORTICULTURE DEVELOPMENT CORPORATION LTD.									
ESTIMATE FOR NEW CONSTRUCTION OF VERMICOMPOST UNIT WITH BAMBOO & TIN SHED STRUCTURE AT AYESHAPUR FARM, NADIA									
SIZE OF TOTAL UNIT = 32.5 SQ. M. (6 NO. OF PITS EACH HAVING DIMENSION OF 4.5 M X 0.9 M)									
Centre Line Length of Vermibed = (3 X 3.200 + 2 X 9.125) = 27.850 m									
ITEM NO.	PAGE REF.	DESCRIPTION OF ITEM	NO.	LENGTH (m)	BREADTH (m)	HEIGHT (m)	QUANTITY	UNIT	AMOUNT (Rs.)
7	SOR (VOL D) PWD (B) P-189 h-1g(9)	Plaster Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over concrete surface] With 1:6 cement mortar 20 mm thick plaster							
		Peripheri Wall Vertical Portion Outside	1	25.650		0.300	7.695	Sq. M.	
		Peripheri Wall Top Portion	1	25.650	0.125		3.206	Sq. M.	
		Inside Partition Wall Top	1	3.200	0.125		0.400	Sq. M.	
		Vermi Bed Inside Vertical	4	10.800		0.225	9.720	Sq. M.	
		Vermi Bed Inside Top	4	4.500	0.250		4.500	Sq. M.	
		Less For Brick Pillar	6	0.250	0.250		-0.375	Sq. M.	
		Add for Brick Pillar	3	1.000		2.100	6.300	Sq. M.	
			3	1.000		2.300	6.900	Sq. M.	
		Drain	1	16.575	0.275		4.558	Sq. M.	
		Vermi wash Pit Vertical + Top	2	2.200	0.725		3.190	Sq. M.	
		Vermi wash Pit bottom	2	0.300	0.300		0.180	Sq. M.	
		Total =					46.274	Sq. M.	₹ 165.00
8	SOR (VOL D) PWD (B) P-192 h-15	Neat Cement Punning Neat cement punning about 1.5mm thick in wall, dado, window sill, floor etc. Cement 0.152 cu m per 100 sq m							
		Total Plastered Area					46.274	Sq. M.	
		Less For Brick Pillar	3	1.000		2.100	-6.300	Sq. M.	
			3	1.000		2.300	-6.900	Sq. M.	
		Total =					33.074	Sq. M.	₹ 34.00
9	Market Rate	Bamboo Truss Construction of Truss by bamboo with necessary fixture & fitting including all materials and labour.							
		Total Area	1	3.450	9.375		32.344	Sq. M.	
		Total =					32.344	Sq. M.	₹ 145.00
10	SOR (VOL D) PWD (B) P-81 h-9	Roof Covering Galvanised corrugated iron sheet work (excluding the supporting frame work) fitted and fixed with 10 mm. dia J or L hook-bolts, limpet and bitumen washers and putty complete with 150 mm. end lap and one corrugation minimum side lap. (Payment to be made on area of finished work) (GCI sheet to be supplied by contractor)							
		Total Area	1	3.450	9.375		32.344	Sq. M.	
		Total =					32.344	Sq. M.	₹ 644.00
Rates quoted from PWD schedule (W.E.F 01.11.2017)								Total	₹ 83,877.57
								GST @18%	₹ 15,097.96
								Sub-Total	₹ 98,975.53
								Cess @1%	₹ 989.76
									₹ 99,965.29
TOTAL (IN WORDS):								R/O	-₹ 0.29
Rupees Ninety Nine Thousand Nine Hundred Sixty Five Only								GRAND TOTAL	₹ 99,965.00

Estimate is vetted.

Chondra

Assistant Engineer (Civil)
W.B.S.F. & H.D.C.L.
(A Govt. of W. B. Enterprise)
Benfish Tower
Salt Lake, Kol-700091

Annexure - II



**WEST BENGAL STATE FOOD PROCESSING
&
HORTICULTURE DEVELOPMENT CORPORATION LIMITED
(A GOVT. OF WEST BENGAL ENTERPRISE)
BENFISH TOWER (6th Floor)
31 - GN Block, Sector - V.
KOLKATA - 700091**

NIQ No. 15/WBSFPHDCL/1770/2025-26

Date: 05-06-2025

Offered Rate:

Sl. No.	Name of the Work	Offered Rate (in Figure)
1	New Construction of Vermicompost Unit at Farm - 2 at Ayeshpur Farm, Nadia	

Offered Rate

(in Words) _____

Date:

Place:

Signature of the Applicant