



**WEST BENGAL STATE FOOD PROCESSING
&
HORTICULTURE DEVELOPMENT CORPORATION LIMITED**
(A GOVT. OF WEST BENGAL ENTERPRISE)
BENFISH TOWER (6th Floor)
31 - GN Block, Sector - V
KOLKATA - 700091

NIQ No. 56/WBSFPHDCL/1870(Pt-3)/2025-26


Date: 20.01.2026

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited from the eligible Contractors / Agencies having experience in similar type of work of **“Civil Works of Proposed Electrical Meter Room Renovation work at premises of AYESH PUR FARM of Department of Food Processing Industries & Horticulture, Govt. of West Bengal at Kalyani Nadia”**. The intending agencies should quote the rate of for this mentioned work at the space provided in Annexure – II. Details of the work is specified in Annexure – I.


TERMS & CONDITION

1. The bidder must submit the copy of Trade License (valid on the last date of submission of the Tender) and PAN & Credential certificate for similar nature of work amounting not below Rs.19000/- in a single work order along with the submission of bid.
2. The rate will be valid for 6(six) months from acceptance of the work order.
3. Rates should be quoted for **“Civil Works of Proposed Electric Meter Room Renovation work at premises of AYESH PUR FARM of Department of Food Processing Industries & Horticulture, Govt. of West Bengal at Kalyani Nadia”** at the mentioned place following the details of work including of all materials, labours, transportation and all taxes in Annexure-II in figure as well as in words.
4. **The Contractors / Agencies may quote their rates against the mentioned work in their letter head Annexure – II and drop the same in a sealed envelope during office hours in the tender box kept at the General Section of WBSFPHDCL office at the above-mentioned address or at The Ayeshpur Farm Office of WBSFPHDCL starting from 21.01.2026 at 12:00 Noon (Date of Publication of NIQ) upto 28.01.2026 by 3:00 PM. Received quotations will be opened on same day at 4:00 PM.**
5. The Work Order is normally be issued to the L-1 Bidder for execution of the work. However, the Quotation Inviting Authority reserves the right to accepting a bid other than the lowest on a specific ground to be recorded in writing.
6. The successful Bidder has to complete the entire work within 15 (fifteen) days from the date of issue of work order.
7. Details may be seen in the office website: www.ipshabengal.com
8. The Corporation reserves the right to accept or reject any or all bids and to annul the tendering process prior to issue of work order, without thereby, incurring any liability to the affected Bidder or Bidders or any liability to inform the Bidder of the ground for such action.
9. **Payment of Bill:**
 - i. Measurement of the work will be taken by the Authority within 5 (five) days from the date of completion of work.
 - ii. Bill will be released to the Contractor within 30 (thirty) days from the date of submission of Bill in duplicate with the certification of the concerned Engineer and copy of duly signed measurement sheet.


Managing Director
W.B.S.F.P. & H.D.C.L.

Annexure – I

WEST BENGAL STATE FOOD PROCESSING & HORTICULTURE DEVELOPMENT CORPORATION LTD.									
Civil Works of Proposed Electric Meter Room Renovation work at premises of AYESH PUR FARM of Department of Food Processing Industries & Horticulture, Govt. of West Bengal at Nalundi Nalla, West Bengal, During the Year 2025-2026									
AREA = 170 SQ. M (1819 SQ. FT.)									
Sl. No.	PAGE REF.	DESCRIPTION OF ITEM	NO.	LENGTH (m)	BREADTH (m)	HEIGHT (m)	QUANTITY	UNIT	AMOUNT (Rs.)
1	NR/2024/1 PWD-01	Clearing occupied premises of shrubs, plants, jungles etc. by cutting and removing as directed (specific permission of Engineer-in-Charge prior to execution will be necessary). (Payment to be made on area cleared)	1.0	6.200	5.520		34.224	Sq. M.	₹ 11.00
2	NR/2024/1 PWD-01	Stripping off worn out plaster and making out joints of walls, ceilings etc. upto any height and in any floor including removing rubbish within a lead of 75 m as directed.							
		Inside Wall:							
		Removal of plaster material	1.0	7.440		2.500	18.600	Sq. M.	
		Inside ceiling plaster removal	1.0	2.200		1.600	3.520	Sq. M.	
		Outside Wall:							
		Outside Wall plaster removal	1.0	8.440		2.800	23.632	Sq. M.	
		Removal of floor	1.0	2.200		1.600	3.520	Sq. M.	
		Total =					49.272	Sq. M.	₹ 15.80
3	NR/2024/1 PWD-01	Chiselling: Plaster (to wall, floor, ceiling etc.) with hand and cement mortar including removing off or chiselling corners as directed and making out joints including chiselling, raising and dip course, scaffolding (where necessary) (Ground floor) (Excluding cost of chipping over concrete surface)							
		(i) Walls 1:5 cement mortar (1st 20 mm thick plaster)	1.0	7.440		2.500	18.600	Sq. M.	
		Inside wall plaster	1.0	8.440		2.800	23.632	Sq. M.	
		Outside wall plaster	1.0	2.200		1.520	3.544	Sq. M.	
		Total =					44.988	Sq. M.	₹ 100.00
4	NR/2024/1 PWD-01	125 mm. thick brick work with 1:4 cement mortar (1:4) in ground floor							
		B/W for window blocking	1.0	0.900		1.600	0.945	Sq. M.	
		Total =					0.945	Sq. M.	₹ 671.00
5	NR/2024/1 PWD-01	Dismantling all types of plain concrete works, stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m.							
		a) In ground floor including roof.	2.0	2.450	1.770	0.125	1.084	Sq. M.	
		Total =					1.084	Sq. M.	₹ 530.04
6	NR/2024/1 PWD-01	Formwork flooring of base concrete with steel base, work & 32 mm down (Jama Khari) (1:5:2:7) (1:5 lime putty:2 work:7 (Jama Khari)							
		(10) 75 mm. thick	1.0	2.450	1.770		4.337	Sq. M.	
		Total =					4.337	Sq. M.	₹ 298.00
7	NR/2024/1 PWD-01	Rendering the Surface of walls and ceiling with White Cement base WATER PROOF wall putty of approved make & brand (1:5 mm thick)							
		(i) Inside wall	1.0	7.440		2.500	18.612	Sq. M.	
		(ii) Inside Ceiling	1.0	2.200		1.720	3.584	Sq. M.	
		(iii) Outside wall	1.0	8.440		2.800	23.632	Sq. M.	
		Total =					44.988	Sq. M.	₹ 122.00
8	NR/2024/1 PWD-01	Applying Interior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Distemper/ Acrylic emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the E.C. (In Ground Floor)							
		(i) Solvent based interior grade Acrylic Primer	1.0	7.440		2.500	18.612	Sq. M.	
		(ii) Inside wall	1.0	2.200		1.520	3.544	Sq. M.	
		(iii) Inside Ceiling							
		Total =					20.456	Sq. M.	₹ 33.70
9	NR/2024/1 PWD-01	Applying Interior grade Acrylic primer of approved quality and brand on plastered or concrete surface old or new surface to receive decorative (smooth finish) (smooth finish) acrylic emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the E.C. (In Ground Floor) (In Two Coats)							
		Outside wall	1.0	8.440		2.800	23.632	Sq. M.	
		Total =					23.632	Sq. M.	₹ 45.10
10	NR/2024/1 PWD-01	Applying Acrylic Emulsion Paint of approved make and brand on walls and ceiling including sand papering in intermediate coats including putty (to be done under specific instruction of Superintending Engineer) (Two coats)							
		(i) Latex Quality					20.456	Sq. M.	₹ 70.00
		Qty same as inside wall and ceiling Primer							₹ 1,431.02
11	NR/2024/1 PWD-01	Protective and Decorative Textured exterior high class matt finish paint of approved quality, composed of special Thermoplastic Resin containing fine crystalline additive (darker than Granite) as per manufacturer's specification and as per direction of E.C. to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer.							
		Two Coats					23.632	Sq. M.	₹ 181.88
		Total =					23.632	Sq. M.	₹ 3,284.83
12	NR/2024/1 PWD-01	Cutting holes and subsequent repairing good damages.							
		(a) Diameter exceeding 200 mm, but not exceeding 450 mm					1.00	Sq. M.	
		(b) In brick work (Concrete-10:1 Kg/M ³)					1.00	Mtr.	₹ 240.00
		Total =					1.00	Mtr.	₹ 240.00



Civil Works of Proposed Electric Meter Room. Renovation work at premises of AYESHIN FARM of Department of Food Processing Industries & Horticulture, Govt. of West Bengal at Kalyani, Nadia, West Bengal. During the Year 2025-2026

AREA = 170 SQ. M. (1929 SQ. FT.)

Swatlow

Prepared By
Junior Engineer (Civil)

Prepared by
Senior Engineer (Civil)

Approved By
Managing Director
WBSFP & NDCL

Annexure - II



**WEST BENGAL STATE FOOD PROCESSING
&
HORTICULTURE DEVELOPMENT CORPORATION LIMITED**
(A GOVT. OF WEST BENGAL ENTERPRISE)
BENFISH TOWER (6th Floor)
31 - GN Block, Sector - V.
KOLKATA - 700091

NIQ No. 56/WBSFPHDCL/1870(Pt-3)/2025-26

Date: 20.01.2026

Offered Rate:

Sl. No.	Name of the Work	Offered Rate (in Figure)
1	Civil Works of Proposed Electrical Meter Room Renovation work at premises of AYESHPUR FARM of Department of Food Processing Industries & Horticulture, Govt. of West Bengal at Kalyani Nadia	

Offered Rate

(in Words) _____

Signature of the Applicant

Date:

Place: