



**WEST BENGAL STATE FOOD PROCESSING
&
HORTICULTURE DEVELOPMENT CORPORATION LIMITED**
(A GOVT. OF WEST BENGAL ENTERPRISE)
BENFISH TOWER (6th Floor)
31 - GN Block, Sector - V
KOLKATA - 700091

NIQ No. **23** /WBSFPDCL/1770/2023-24

Date: 26.04.2023

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited from the eligible Contractors / Agencies having experience in similar type of work of "Repair of Boundary Wall" at Ayeshpur Farm, Dist. - Nadia. The intending agencies should quote the rate of "Repair of Boundary Wall" measuring approx. 23 m length at the space provided in Annexure - I.

Scope & Quantity of Work is described below:

ITEM NO.	PAGE REF.	DESCRIPTION OF ITEM	NO.	LENGTH (m)	BREADTH (m)	HEIGHT (m)	QUANTITY	UNIT
1	SOR (VOL I) PWD (B) P - 42 It - 36(c)	Shuttering Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) Steel shuttering or 9 to 12 mm thick approved quality ply board shuttering in any concrete work.						
		R. C. C. at Bottom Beam	2	23.000		0.250	11.500	Sq. M.
		Total =						11.500
2	SOR (VOL I) PWD (B) P - 43 It - 40 (a) (i) (I)	Reinforcement Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16gauge black annealed wire at every intersection, complete as per drawing and direction. For works in foundation and upto roof of ground floor/upto 4 m Tor steel/Mild Steel SAIL/ TATA/RINL						
		Bottom Beam -10φ (Top & Bottom Layer)	4	23.100			0.057	MT
		8φ Stirrup	116	0.928			0.043	MT
		Total =						0.100

3	SOR (VOL I) PWD (B)	P - 24 It - 5(i)	R. C. C. Controlled Cement concrete with well graded stone chips (20 mm nominal size) excluding shuttering and reinforcement with complete design of concrete as per IS : 456 and relevant special publications, submission of job mix formula after preliminary mix design after testing of concrete cubes as per direction of Engineer-in charge. Consumption of cement will not be less than 300 Kg of cement with Super plasticiser per cubic meter of controlled concrete but actual consumption will be determined on the basis of preliminary test and job mix formula. In ground floor and foundation. [using concrete mixture] M 20 Grade Pakur Variety						
			Bottom Beam	1	23.000	0.250	0.250	1.438	Cu. M.
			Coping at Top of Wall	1	23.000	0.250	0.025	0.144	Cu. M.
								1.581	Cu. M.
4	SOR (VOL I) PWD	P - 15 It - 7(b)	One Brick th. Brick Work Brick work with 1st class bricks in cement mortar (1:4) In superstructure, ground floor						
				8	0.250	0.250	1.750	0.875	Cu. M.
								Total = 0.875	Cu. M.
			Less for Supply of Brick from Farm	-1	0.875		389	-341.000	Nos.
5	SOR (VOL I) PWD (B)	P - 16 It - 16	Half Brick th. Brick Work 125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor.						
			125 th. Brick wall	1	21.000		1.750	36.750	Sq. M.
								Total = 36.750	Sq. M.
			Less for Supply of Brick from Farm	-1	36.750	0.125	389	-1787.000	Nos.
6	Market Rate		Carrying & Cleaning of Bricks Carrying of brick from different location of farm, stacking them at the work site & cleaning of the same bricks before using in construction						
			Total Brickwork	2128				2128.000	Nos.
								Total = 2128.000	Nos.
7	SOR (VOL I) PWD (B)	P - 189 It - 1(i)(b)	Plaster Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] With 1:6 cement mortar 20 mm thick plaster						
			Wall Side	2	23.000		2.000	92.000	Sq. M.
				16	0.125		2.000	4.000	Sq. M.
								(Marked A) Total = 96.000	Sq. M.
8	SOR (VOL I) PWD (B)	P - 196 It - 8(a)	Primer on Wall Applying Exterior grade acrylic primer of approved quality and brand on plastered or concrete surface old or new surface to receive decorative textured (matt finish) or smooth finish acrylic exterior emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the EIC. In Ground Floor: One Coat						
			Marked A					96.000	Sq. M.
								Total = 96.000	Sq. M.

9	SOR (VOL I) PWD (B)	P - 197 It - 17(a)	Painting on Wall						
Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer. In Ground floor (Two Coat) Normal Acrylic Emulsion									
			Marked A					96.000	Sq. M.
								Total = 96.000	Sq. M.

TERMS & CONDITION

1. The bidder must submit the copy of Trade License (valid on the last date of submission of the Tender) and PAN along with the submission of bid.
2. The rate will be valid for 6(six) months from acceptance of the work order.
3. Rates should be quoted for "Repair of Boundary Wall" at the mentioned place following the above scope of work including of all materials, labours, transportation and all taxes in Annexure-I in figure as well as in words.
4. The intending quotation may quote their rates against the mentioned work in Annexure - I and drop the same in a sealed envelope during office hours in the tender box kept at the General Section of WBSFPHDCL office at the above mentioned address or at The Ayeshpur Farm Office of WBSFPHDCL upto 02.05.2023 by 3:00 PM. Received quotations will be opened on same day at 4:00 PM.
5. Generally the Work Order will be issued to the L-1 Quotationer for execution of the work following the specification mentioned above. However, the accepting authority reserves the right to reject any of all the quotations even the lowest one, without assigning any reason thereof.
6. The successful Bidder has to complete the entire work within 7 (seven) days from the date of issue of work order.
7. Details may be seen in the Office Notice Board.
8. The Corporation reserves the right to accept or reject any or all bids and to annul the tendering process prior to issue of work order, without thereby, incurring any liability to the affected Bidder or Bidders or any liability to inform the Bidder of the ground for such action.
9. After successful completion of work, bill will be released to the Contractor within 30 days from the date of submission of Bill in duplicate duly certified by the officials.



Managing Director
W.B.S.F.P. & H.D.C.L.

NIQ No. **23** /WBSFPHDCL/1770/2023-24

Date: 26.04.2023

Copy to:

1. The B.D.O. Office, Haringhata with a request to display the Notice in the Office Notice Board.
2. The Prodhan, Birohi - I G.P. with a request to display the Notice in the Office Notice Board.
3. The Prodhan, Birohi - II G.P. with a request to display the Notice in the Office Notice Board.
4. The Farm In-Charge with a request to display the Notice in the Office Notice Board.
5. Notice Board of the office


Managing Director
W.B.S.F.P. & H.D.C.L.

Annexure - I



**WEST BENGAL STATE FOOD PROCESSING
&
HORTICULTURE DEVELOPMENT CORPORATION LIMITED**
(A GOVT. OF WEST BENGAL ENTERPRISE)
BENFISH TOWER (6th Floor)
31 - GN Block, Sector - V.
KOLKATA - 700091

NIQ No. **23** /WBSFPHDCL/1770/2022-23

Date: 26.04.2023

Sl. No.	Name of the Work	Offered Rate of Construction (in Figure)
1	Repairing of Boundary Wall at Ayeshpur Farm, Dist. - Nadia measuring approx. 23 metre in length.	

Offered Rate of Construction

(in Words) _____

Date:

Place:

Signature of the Applicant